BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT52490

APPROVED SCHEDULE - B

No. EE/BTP/BBMP/E-PMT/10/2022-23, Dated: 04-07-2022.

Name of Work: PACKAGE NO. 07 (CONSISTS OF 7 WORKS)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri K LAKSHMI NARAYANA REDDY ( )	
				In Figures	In Words
1	2256.9	Removing and resetting Stone Slab of drain and pointing in C.M (1:3) (Approved Rate)	Sqm	139.72	Rupees One Hundred Thirty Nine and Seventy One Paise Only
2	1522.8	Removing and Resetting of Footpath Slab and pointing in C.M (1:3) (Approved Rate)	Sqm	271.35	Rupees Two Hundred Seventy One and Thirty Four Paise Only
3	6299.2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (V	Cum	351.02	Rupees Three Hundred Fifty One and One Paise Only
4	648.54	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	6413.04	Rupees Six Thousand Four Hundred Thirteen and Three Paise Only
5	86.73	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Ton	106425.93	Rupees One Hundred Six Thousand Four Hundred Twenty Five and Ninety Three Paise Only
6	1333.2	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-1,P.No.17, I.No.2.4.2 of PWD SR 2021-22)	Cum	7235.62	Rupees Seven Thousand Two Hundred Thirty Five and Sixty Two Paise Only
7	655.87	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6613.95	Rupees Six Thousand Six Hundred Thirteen and Ninety Four Paise Only

K. Reddy

Signature of the Contractor

Executive Engineer

Name of Work: PACKAGE NO. 07 (CONSISTS OF 7 WORKS)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri K LAKSHMI NARAYANA REDDY ( )	
				In Figures	In Words
8	369	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead Dismantling Brick / Tile work / rubble masonry / pitching / etc by mechanical means	Cum	155.88	Rupees One Hundred Fifty Five and Eighty Eight Paise Only
9	440.64	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6260.62	Rupees Six Thousand Two Hundred Sixty and Sixty Two Paise Only
10	77.76	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) Using Available Stone.	Cum	4445.48	Rupees Four Thousand Four Hundred Forty Five and Forty Seven Paise Only
11	1568	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge.	Sqm	229.78	Rupees Two Hundred Twenty Nine and Seventy Seven Paise Only
12	2213.2	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1225.10	Rupees One Thousand Two Hundred Twenty Five and Ten Paise Only
13	6977.3	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work	Sqm	2174.98	Rupees Two Thousand One Hundred Seventy Four and Ninety Seven Paise Only
14	522.24	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	5287.34	Rupees Five Thousand Two Hundred Eighty Seven and Thirty Three Paise Only
15	269.19	Providing B S slabs of selected quality roughly dressed having a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)	Sqm	966.46	Rupees Nine Hundred Sixty Six and Forty Five Paise Only
16	4964	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (Approved Rate)	Nos	532.20	Rupees Five Hundred Thirty Two and Nineteen Paise Only
17	1093.8	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	98.15	Rupees Ninety Eight and Fourteen Paise Only
18	1717.6	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work	Cum	75.05	Rupees Seventy Five and Five Paise Only

K. Lucy

Signature of the Contractor

Executive Engineer

Name of Work: PACKAGE NO. 07 (CONSISTS OF 7 WORKS)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri K LAKSHMI NARAYANA REDDY ( )	
				In Figures	In Words
19	1545.8	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2764.28	Rupees Two Thousand Seven Hundred Sixty Four and Twenty Seven Paise Only
20	10830	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means.	Sqm	48.50	Rupees Forty Eight and Forty Nine Paise Only
21	33199	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom	Sqm	13.86	Rupees Thirteen and Eighty Five Paise Only
22	647.3	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.	Cum	10552.53	Rupees Ten Thousand Five Hundred Fifty Two and Fifty Two Paise Only
23	1268.5	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects	Cum	12252.20	Rupees Twelve Thousand Two Hundred Fifty Two and Twenty Paise Only
24	1112.4	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.	Sqm	551.93	Rupees Five Hundred Fifty One and Ninety Three Paise Only
25	84	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel	Cum	487.27	Rupees Four Hundred Eighty Seven and Twenty Seven Paise Only
26	72	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates	Cum	5610.54	Rupees Five Thousand Six Hundred Ten and Fifty Four Paise Only
27	72	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.	Cum	7519.21	Rupees Seven Thousand Five Hundred Nineteen and Twenty One Paise Only

Signature of the Contractor

Executive Engineer

Name of Work: PACKAGE NO. 07 (CONSISTS OF 7 WORKS)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri K LAKSHMI NARAYANA REDDY ( )	
				In Figures	In Words
28	10438	Cost of Haulage Excluding Loading and Unloading Taking output 25 t load and lead 10 km = 250 t.km	T.km	110.85	Rupees One Hundred Ten and Eighty Four Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92.